

RFP 325 LEWIS DRIVE DEMOLITION AND REMEDIATION ADDENDUM #1

Date of Addendum: April 20, 2026

QUESTION AND ANSWERS

The following questions and answers are provided as a matter of information to clarify issues raised about the RFP. Respondents should take this Addendum into consideration when preparing and submitting their Proposal.

Question 1: Is 3-inch minus pit run acceptable as backfill?

Answer: Yes

Question 2: Is there going to be compaction testing done on what needs to be backfilled?

Answer: There is no requirement for proctor testing for soil compaction. The expectation is that backfilling be placed in even lifts not exceeding 300 mm, free of voids, and compacted. Proof rolling will be the accepted quality control method to verify acceptable compaction prior to placement of the topsoil cap.