

ADDENDUM #2

Would CQC require a bond to perform this work for the City of Quesnel?

Yes, as per the RFP: 'A Labour and Material Payment Bond, and a Performance Bond will be required, each in 50% of the contract price. A Bid Bond is not required.'

The unit price breakdown and contract price in the Schedule of Prices provided by the Proponent as part of the Proposal will be incorporated in the CCDC 4 contract. All overhead costs including required bonding, insurance and otherwise should be incorporated into the Schedule of Prices.'

Water management – Water and cuttings produced during the drilling and development process shall be managed

Water and cuttings need to be managed so as not to leave the property in significant volumes. We do not expect a break tank will be necessary as cuttings can be left onsite

What defines turbidity and control of well cuttings will there be a dumping station?

Acceptable levels of turbidity in the well following development will be determined by the onsite hydrogeologist during the development program. Control of well cuttings refers to controlling the direction of discharge to adjacent the drill rig. For example: do not allow cuttings to shoot onto the street or dog park from an air rotary rig.

Will Turbidity readings be required?

Turbidity will be monitored by the onsite hydrogeologist and is not the responsibility of the drilling contractor.